

DETAILED ESTIMATE



ZILLA PARISHAD NASIK

(B.&C.) DIVISION NO: 3

SUB-DIVISION (B&C) NIPHAD

NAME OF WORK: Constructing Cement Concrete road in krushi Nagar (Ward No:- 1)
at village Lasalgaon Tal Niphad Dist - Nasik

EST. COST 999979.00 ONLY

T.S.NO/DA

A.A.NO/

JOB NO.

15 th fin comm (G P LEVEL)
2024-25

ESTIMATE

YEAR 2024-25

DIVISION (B.&.C.) DIVISION NO:

SUBDIVISION SUB-DIVISION (B&C)

SANCTIONED ESTIMATE NO

FUND HEAD 15 th fin comm (G P LEVEL)

MAJOR HEAD

MINOR HEAD

SERVICE HEAD

DEPARTMENTAL HEAD

THIS ESTIMATE IS FRAMED IN THE OFFICE OF EXECUTIVE ENGINEER,Z.P.(B.&.C.) DIVISION ZILLA
PARISHAD NASIK.THE PROBABLE EXPENSES THAT WILL BE INCURRED ON THE WORK NAMED BELOW
:-

NAME OF WORK: Constructing Cement Concrete road in krushi Nagar (Ward No:- 1) at village
Lasalgaon Tal Niphad Dist - Nasik

ESTIMATED COST Rs: **999979.00** ONLY

TECHNICALLY SANCTIONED UNDER
NO

ADMINISTRATIVELY APPROVED UNDER
NO

ESTIMATE PREPARED BY Engr.Shri. N B PATIL Sectional Engineer

ESTIMATE CHECKED BY Engr.Shri. R U PURI Deputy Engineer

CALL OR AUTHORITY:-

GENERAL DISCRIPTION

AS PER SEPERATE SHEET ATTACHED

NAME OF WORK: Constructing Cement Concrete road in krushi Nagar (Ward No:- 1) at village Lasalgaon Tal Niphad Dist - Nasik

RECAPULATION SHEET

Sr.No.	DESCRIPTION	% CONSIDERED	AMOUNTR s-Ps.	REMARK.
	2	3	4	5

1	Cost of work proper	999479.00
---	---------------------	-----------

2	SQM and Contegencies	0.00	%	500.00
---	----------------------	------	---	--------

					Total Rs-Ps	999979.00	
--	--	--	--	--	-------------	------------------	--

say Rs. **999979.00**

SECTIONAL ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

DEPUTY ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

NAME OF WORK: Constructing Cement Concrete road in krushi Nagar (Ward No:- 1) at village Lasalgaon Tal Niphad Dist - Nasik

ABSTRACT

Sr..No.	DESCRIPTION OF ITEM		QTY	UNIT	RATE Rs.-Ps.	AMOUNT Rs.-PS.
1	2		3	4	5	6
1	Picking the road surface including sectioning etc. complete (BT surface.)	0	332.40	One Square Metre	44.00	14625.60
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including	MORTH 404	26.80	One Cubic Metre	2736.01	73325.07
3	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate (natural sand/	MORTH 601	35.73	One Cubic Metre	4278.83	152882.60
4	Providing and laying in-situ M30 Grade unreinforced plain cement concrete pavement over a prepared sub base with 43	MORTH 602	66.48	One Cubic Metre	8355.83	555495.58
5	Supplying hard murum/ kankar at the road site, including conveying and stacking complete.	0	6.64	One Cubic Metre	765.77	5084.71
6	Spreading hard murum/ soft murrum/ gravel or kankar for side width complete	0	6.64	One Cubic Metre	79.00	524.56
7	Providing expansion joints with 25mm thick bituminous pad as per detailed drawings etc. complete.	BR.43 Page Number 138	11.08	One Square Metre	1086.00	12032.88
8	Providing and fixing board displaying information, such as 'Name of work, Tender cost, Name of Contractor, Work completion	MORTH 801	1.00	One Number	9963.00	9963.00
					TOTAL	823934.00
	Add For GST			18.00	%	148308.00
	Add Labour Insurance			0.50	%	4120.00
					TOTAL	976362.00
9	Royalty Charges (sand)		48.04	Cubic Metre	237.37	11403.25
10	Royalty Charges (others)		40.14	Cubic Metre	216.18	8677.47
11	laboratory charges		3036.00	for all test	1.00	3036.00
					TOTAL RS.	999479.00

SECTIONAL ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

DEPUTY ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

NAME OF WORK:Constructing Cement Concrete road in krushi Nagar (Ward No:-
1) at village Lasalgaon Tal Niphad Dist - Nasik**MEASUREMENT**

I. No.	DESCRIPTION OF ITEM	No.	L.	B/W	H/D.	TOTAL	UNIT
1	2	3	4	5	6	7	8
1	Picking the road surface including sectioning etc. complete (BT surface.)						
	Ex. For road level	1	83.10	4.00		332.40	
					TOTAL	332.40	
				Total	Qty.	332.40	One Square Metre
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing to proper grade						
	below CC	1	83.10	4.00	0.075	24.93	
					TOTAL	24.93	
				Total	Qty.	26.80	One Cubic Metre
3	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate (natural sand/ VSI grade finely washed crushed sand) conforming to IS:						
	Base course	1	83.10	4.00	0.100	33.24	
					TOTAL	35.73	One Cubic Metre
4	Providing and laying in-situ M30 Grade unreinforced plain cement concrete pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate (natural sand/ VSI grade finely washed crushed sand) conforming to IS 383, using fine and coar						
	wearing coarse	1	83.10	4.00	0.200	66.48	
					TOTAL	66.48	One Cubic Metre
5	Supplying hard murum/ kankar at the road site, including conveying and stacking complete.						
	concrete edge side width	2	83.10	0.40	0.100	6.64	
					TOTAL	6.64	One Cubic Metre
6	Spreading hard murum/ soft murrum/ gravel or kankar for side width complete						
	qty as per item no:- 5					6.64	
					TOTAL	6.64	One Cubic Metre

I. No.	DESCRIPTION OF ITEM	No.	L.	B/W	H/D.	TOTAL	UNIT
7	Providing expansion joints with 25mm thick bituminous pad as per detailed drawings etc. complete.						
		1	83.10 3.00	4.00	0.100	11.08	
				Total	Qty.	11.08	One Square Metre
8	Providing and fixing board displaying information, such as 'Name of work, Tender cost, Name of Contractor, Work completion and liability period etc', having rectangular shape of 1.20m x 0.60m						
		1				1.00	
				Total	Qty.	1.00	One Number
9	Royalty Charges (sand)						
	Dry L.C	1	35.73	0.47		16.79	
	C.C. M-20	1	66.48	0.470		31.25	
				Total	Qty.	48.04	Cubic Metre
10	Royalty Charges (others)						
	soling	1	26.80	1.25		33.50	
	murum	1	6.64	1.00		6.64	
				Total	Qty.	40.14	Cubic Metre
11	laboratory charges						
	cement	1		771.00		771.00	
	cube	2		770.00		1540.00	
	GR 2	1		725.00		725.00	
	hm	0		1306.00		0.00	
				Total	Rs'	3036.00	for all test

SECTIONAL ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

LEAD CHARGES STATEMENT

ntn 25/7/22

Name Of Work -

Constructing Cement Concrete road in krushi Nagar (Ward No:-
1) at village Lasalgaon Tal Niphad Dist - Nasik

Type of Material	Lead In Km s	Lead Charges Rs.	SOURCE
Concrete Blocks	0.00	#N/A	Local
Murum, Building Rubish, Earth	10.00	330.77	Local
Excavated Rock soling stone	3.00	280.83	Local
Bricks 1000 nos 1cum=500 Bricks	5.00	531.38	Local
cement	8.00	208.43	Local
sand	40.00	767.42	Local
Stone below 40 mm, Normal Brick sider aggre. Timber crush metal	12.00	372.03	Local
Stone aggregate 40mm Normal size and above	12.00	356.53	Local
Tiles Half Round Tiles / Roofing Tiles / Manglore Tiles	5.00	329.98	Local
Steel (MS, TMT, H.Y.S.D.)	8.00	208.43	Local
Structural Steel	0.00	#N/A	Local
Flooring Tiles Ceramic/ Marbonate	0.00	#N/A	Local
Asphalt . Rs. 10.00 / MT/Km	0.00	0.00	Refinery

SECTIONAL ENGINEER

Z.P.(B&C)SUB-DIVISION NIPHAD

DEPUTY ENGINEER

Z.P.(B&C)SUB-DIVISION NIPHAD

Name of work Constructing Cement Concrete road in krushi Nagar (Ward No:- 1) at village Lasalgaon Tal Niphad Dist - Nasik

RATE ANALYSIS

Sr. No.	S.S.R. Item No.	Description of the Item in Brief	Unit	Basic Rate (Rs.Ps.)	deduct for scada	Net amount after deductng scada (5 6)	Type of material requ- ired	Qty of material reqd	Net lead charges	Total lead charges (Rs.Ps)	Total (Rs. Ps.) (7+11)	TRIBAL 10% --Non Trbal 0%	Net Total Amount (Rs. Ps.) (12+13)	specificati ons
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	2.33	Picking the road surface including sectioning etc. complete (BT surface.)	One Square Metre	44.00		44.00				0.00	44.00	0.00	44.00	0
2	3.20	Providing, laying, spreading and compacting stone aggregates of specific sizes to water	One Cubic Metre	2180.00	0.00	2180.00	matal	1.21	372.03	450.16	2736.01	0.00	2736.01	MORTH 404
							murum	0.32	330.77	105.85				
									Total	556.01				
3	5.13	Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate (natural sand/ VSI grade finely washed crushed sand) conforming to IS:	One Cubic Metre	3659.00	126.00	3533.00	cement	0.17	208.43	35.43	4278.83	0.00	4278.83	MORTH 601
							sand	0.47	767.42	360.69				
							cr.metal	0.94	372.03	349.71				
									Total	745.83				
4	5.04	Providing and laying in-situ M30 Grade unreinforced plain cement concrete pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate (natural sand/ VSI	One Cubic Metre	7736.00	126.00	7610.00	cement	0.17	208.43	35.43	8355.83	0.00	8355.83	MORTH 602
							sand	0.47	767.42	360.69				
							cr.metal	0.94	372.03	349.71				
									Total	745.83				
5	2.29a	Supplying hard murum/ kankar at the road site, including conveying and stacking complete.	One Cubic Metre	435.00	0.00	435.00	murum	1.000	330.77	330.77	765.77	0.00	765.77	0
6	2.30	Spreading hard murum/ soft murrum/ gravel or kankar for side width complete	One Cubic Metre	79.00	0.00	79.00				0.00	79.00	0.00	79.00	0
7	14.33	Providing expansion joints with 25mm thick bituminous pad as per detailed drawings etc. complete.	One Square Metre	1086.00	0.00	1086.00				0.00	1086.00	0.00	1086.00	BR.43 Page Number 138
8	6.36	Providing and fixing board displaying information, such as 'Name of work, Tender cost, Name of Contractor, Work completion and liability period	One Number	9963.00	0.00	9963.00				0.00	9963.00	0.00	9963.00	MORTH 801

Sr. No.	S.S.R. Item No.	Description of the Item in Brief	Unit	Basic Rate (Rs.Ps.)	deduct for scada	Net amount after deductng scada (5 6)	Type of material requ- ired	Qty of material reqd	Net lead charges	Total lead charges (Rs.Ps)	Total (Rs. Ps.) (7+11)	TRIBAL 10% --Non Trbal 0%	Net Total Amount (Rs. Ps.) (12+13)	specificati ons
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
9		Royalty Charges (sand)	Cubic Metre	237.37		237.37			0.00	0.00	237.37	0.00	237.37	
10		Royalty Charges (others)	Cubic Metre	216.18		216.18			0.00	0.00	216.18	0.00	216.18	
11		laboratory charges	for all test	1.00		1.00			0.00	0.00	1.00	0.00	1.00	



SECTIONAL ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD

DEPUTY ENGINEER
Z.P.(B&C)SUB-DIVISION NIPHAD